



- NOTES:**
1. TOWER/ANTENNA ASSEMBLY AND FOUNDATION CONSTRUCTION MUST MEET CURRENT EDITION FLORIDA BUILDING CODE WIND LOAD REQUIREMENTS. PROVIDE STRUCTURAL CERTIFICATION BY FLORIDA REGISTERED LICENSED PROFESSIONAL ENGINEER.
  2. TELEMETRY NOT REQUIRED FOR PUMP STATIONS WITH PRIVATE OWNERSHIP AND MAINTENANCE.

CONCRETE BASE. SIZE TO BE DETERMINED BY LICENSED STRUCTURAL ENGINEER PER SOIL CONDITIONS AND FLORIDA BUILDING CODE WIND LOAD REQUIREMENTS (SEE NOTE).

**TELEMETRY ANTENNA MOUNT DETAIL**